

July 15, 2026

QUOTE# E-HOOVEN06122026RC-rev

HOOVEN CO
Seth Adams
707-601-6694
Electrical Operations Manager

RE: Franklin Generator & ATS + Startup – Humboldt County – Updated per Addendum

Thank you for the opportunity to provide pricing for the generator set and system accessories for the above-mentioned project. We are pleased to quote as follows:

ITEM 1: Equipment

One (1) Gillette 400kW Standby Generator

- SP-4000 / 400kW Standby Generator
- 400kW, 0.8PF
- NFPA 110
- UL 2200
- 480V, 3 Phase, 4 Wire, 60 Hertz, 1800 RPM
- Outdoor Sound Attenuated Enclosure
- DeepSea 7420 MKII Controller
- Relay Expansion Package
- Remote Annunciator
- Hidden Critical Grade Silencer Mounted to Engine
- 2 Year / 2000 Hour Limited Warranty
- Batteries, Rack and Charger
- **Estimated Lead Time is 18-20 Weeks**

One (1) ASCO 7000 600A Bypass Transfer Switch

- 7000 Series
- Automatic Open Transition Bypass Switch
- 480V, 3 Phase, 3 Pole, 4 Wire
- Outdoor NEMA 3RX(S)-UL Stainless Steel Secure Enclosure (See Disclaimers)
- See Included Accessories Below
- **Estimated Lead Time is 24-26 Weeks**

Sacramento Branch:
4372 Pinell Street
Sacramento, California 95838
Phone 916.564.2622

Headquarters:
150 Nardi Lane
Martinez, California 94553
Phone 925.229.2700
Fax 925.229.2702

Reno Branch:
1395 Spice Islands Drive
Sparks, Nevada 89431
Phone 775.331.4151

#	ACCESSORY DESCRIPTIONS	
	Accessory Code	Description
1	31BG	Group 5: Status Relay Bundle - Provides 1 relay (3 total) for each of the following statuses, Normal Source Acceptability, Emergency Source Acceptability, Pre & Post Transfer Signal. Each relay has 2 NO/NC (Form C) sets of contacts rated for 6A at 120Vac, 250Vac Max. Group Q: "STANDARD 2A, 30VDC. This is for additional ratings Status Relay Bundle - Provides 1 relay (3 total) for each of the following statuses, Normal Source Acceptability, Emergency Source Acceptability, Pre & Post Transfer Signal. Each relay has 2 NO/NC (Form C) sets of contacts rated for 6A at 120Vac, 250Vac Max."
2	125A	This Product Meets Or Exceeds The Requirement Of The International Building Code For Importance Factor 1.5 Electrical Equipment. For Use In Zone 4 Or Less Severe Seismic Regions. Consult ASCO for details

ITEM 2: Scope of Work

- Supply Above Equipment
- Supply Engineered Submittal Package & Support
- Freight to Job Site, Offload and Set by Others
- Start Up/Commissioning w/ 2 Hour Load Bank
- Training at Startup
- Factory Warranty Initiation

Freight Estimate: Transfer Switch- - - - -

Freight Estimate: Generator to Reno - - - -

Delivery to Eureka, CA, from Reno includes a crane to set unit

**All Freight pricing given is an estimate only! Actual freight will be calculated at the time of shipment and added to the invoice. If the equipment is received by CD & Power and delivered at a future date an additional delivery charge will be applied*.*

Possible Adders NOT included in above pricing:

- Stairs & Platform: (Budgetary – Advise sourcing elsewhere considering location)
- Rental Generator and/or ATS (inquire for price)
- Remove ATS from BOM/Total: Estimated \$ in Freight
- AQMD Application & Approval (Fees by Owner/Customer):

CD & Power Quotation Notes:

- Above estimated lead time after receipt of order & signed submittal is returned
- Delivery time is an estimate and subject to change
- No equipment will be ordered without written release to proceed – price changes issued by the manufacturer after quotation validity and prior to release will be passed along to the customer
- **All fueling and connections must be terminated prior to technician arrival for start up**
- All products require factory start up by certified technician
- Generator Factory Submittals can be provided in 5-7 weeks from receipt of order
- Installation is not included